

# Aviva Plant and Inspection Guide

## Lift and Crane

Plant/Equipment Type	Frequency	Legislation
Forklift Trucks	12 months (6 months if person lifted)	SI No. 299 of 2007 (PT2-Ch3)
Tower Crane/Self Erectors	12 months	SI No. 299 of 2007 (PT2-Ch3)
General cranes	12 months	SI No. 299 of 2007 (PT2-Ch3)
Passenger/Goods Lifts	6 months	SI No. 299 of 2007 (PT2-Ch3)
Lifting Tackle/Accessories	6 months	SI No. 299 of 2007 (PT2-Ch3)
Lifting machines	12 months	SI No. 299 of 2007 (PT2-Ch3)
Cranes	12 months	SI No. 299 of 2007 (PT2-Ch3)
Lorry Mounted Cranes	12 months	SI No. 299 of 2007 (PT2-Ch3)
Mobile Cranes	12 months	SI No. 299 of 2007 (PT2-Ch3)
Vehicle Lifting Tables	12 months	SI No. 299 of 2007 (PT2-Ch3)
High Lift Pallet Trucks/Stackers	12 months	SI No. 299 of 2007 (PT2-Ch3)
Vehicle Tail Lifts	12 months	SI No. 299 of 2007 (PT2-Ch3)
Teleporters	12 months (6 months if person lifted)	SI No. 299 of 2007 (PT2-Ch3)
Mobile Elevated Work Platforms	6 months	SI No. 299 of 2007 (PT2-Ch3)
Window Cleaning Platforms	6 months	SI No. 299 of 2007 (PT2-Ch3)
Dock Levelers	12 months	SI No. 299 of 2007 (Section 30)
Pallet Trucks	12 months	SI No. 299 of 2007 (Section 30)
PPE Body Harness and Lanyards	6 months	SI No. 299 of 2007 (Section 30)
Escalators/Travelators	12 months	SI No. 299 of 2007 (Section 30)
Excavator	12 months	SI No. 299 of 2007 (Section 30) or (PT2-Ch3) if used as crane
Dumper trucks	12 months	SI No. 299 of 2007 (Section 30)
Loading Shovels	12 months	SI No. 299 of 2007 (Section 30)
Hydraulic Jacks	12 months	SI No. 299 of 2007 (Section 30)

## Electrical

Plant/Equipment Type	Frequency	Legislation
Motors	Recommended as 12 months	SI No. 299 of 2007 (Part 3)
Transformers	Recommended as 12 months	SI No. 299 of 2007 (Part 3)
Supply Panels	Recommended as 12 months	SI No. 299 of 2007 (Part 3)
Fixed Electrical Installations	Recommended as 12 months	SI No. 299 of 2007 (Part 3)
Generators	Recommended as 12 months	SI No. 299 of 2007 (Part 3)
Portable Power Tools	Recommended as 12 months	SI No. 299 of 2007 (Part 3/Section 30)
Hazardous Area Electrical Installation	Various depending on Legislation	SI No. 299 of 2007 (Part 8)

SI No. 299 - Safety, Health and Welfare at Work (General Application) Regulations 2007 (As Amended).

The contents of this guide are for general information purposes only. Whilst Aviva endeavours to ensure that the information on this site is correct, no warranty, express or implied, is given as to its accuracy and Aviva does not accept any liability for error or omission. Visit: <http://www.aviva.ie/business-insurance/products/engineering-services/> for further details.

## Pressure Plant

Plant/Equipment Type	Frequency	Legislation
Air Receivers	26 months	SI No.445 of 2012
Pressurised Tanks	26 months	SI No.445 of 2012
Autoclaves	26 months	SI No.445 of 2012
Autoclaves -Steam Generating	14 months	SI No.445 of 2012
Hot Water/Heating Boilers <110C	12 months	SI No. 299 of 2007 (Section 30)
Hot Water/Heating Boilers >110C	14 months	SI No.445 of 2012
Steam Boilers	14 months	SI No.445 of 2012
Blowdown Vessel	26 months	SI No.445 of 2012
Café Boilers	14 months	SI No.445 of 2012
Calorifiers	26 months	SI No.445 of 2012
Jacketed Reactor Vessel	26 months	SI No.445 of 2012
Jacketed Process Vessels	26 months	SI No.445 of 2012
Steam Vessels	26 months	SI No.445 of 2012
Process Vessels	26 months	SI No.445 of 2012
Pressurisation Units	26 months	SI No. 299 of 2007 (Section 30)
Refridgeration/Air Conditioning Units (> 25kW)	26 months	General Apps (SI No.445 of 2012)
Refridgeration/Air Conditioning Units (>>25kW)	26 months	SI No. 299 of 2007 (Section 30)
LPG Storage Tanks	12 months as per WSE	SI201 of 1990 Storage of LPG, using UKLPG Code of Practices and ISEN12819 2009
LPG Road Tankers	12 months as per WSE	2010 TPED Transportable Pressure Equipment Directive SI 349 of 2011

## Work Equipment

Plant/Equipment Type	Frequency	Legislation
Roof Fall Protection System	12 months	SI No. 299 of 2007 (Section 30)
Road Retexturing Vehicles/ Machinery	12 months	SI No. 299 of 2007 (Section 30)
Rock Crusher	12 months	SI No. 299 of 2007 (Section 30)
Power Screen	12 months	SI No. 299 of 2007 (Section 30)
Combined Heat and Power Plant	12 months	SI No. 299 of 2007 (Section 30)
Hydraulic Compactor	12 months	SI No. 299 of 2007 (Section 30)
Stone Drilling Rig	12 months	SI No. 299 of 2007 (Section 30)
Chipper	12 months	SI No. 299 of 2007 (Section 30)
Roller	12 months	SI No. 299 of 2007 (Section 30)
Loader/Backhoe	12 months	SI No. 299 of 2007 (Section 30)
Pile Driver	12 months	SI No. 299 of 2007 (Section 30)
Block Layer	12 months	SI No. 299 of 2007 (Section 30)
Block Strapping Machine	12 months	SI No. 299 of 2007 (Section 30)
Ladder	12 months	SI No. 299 of 2007 (Section 30)
Mobile Steps	12 months	SI No. 299 of 2007 (Section 30)
Working Platform	12 months	SI No. 299 of 2007 (Section 30)
Palletising Machine	12 months	SI No. 299 of 2007 (Section 30)
Pallet Invertor	12 months	SI No. 299 of 2007 (Section 30)
Tractors	12 months	SI No. 299 of 2007 (Section 30)
Agricultural Machinery	12 months	SI No. 299 of 2007 (Section 30)
Pallet Racking	12 months	SI No. 299 of 2007 (Section 30)